



- Notes:
1. Concrete 32 Mpa. Air 5-7%
 2. Approx. weight 6800 lbs.
 3. Unit can be set in place if site Is ready at time of delivery.

U.D. VAULT ASSEMBLY Base, Box Section and Frame

Acton Precast Concrete Limited

RR 2 Acton 1-800-461-1516 Fax (519) 853-1324